

Civil Site Work, Compressed Air Energy Storage, Core Well Drilling Program, Various Counties, California

Pacific Gas & Electric (PG&E)

Value: \$4.8M

Location: Yolo, Solano, and San Joaquin Counties, California

Period of Performance:

1/2013 – 6/2013

Client: PG&E

- Graded and improved existing gravel roads and compacted existing roads
- Construction staking of drill pad
- Placed 24" construction zone fencing around drill pad perimeter to delineate work area and biological boundaries
- Cleared, grubbed, scarified, moisture conditioned and compacted subgrade
- Constructed an approximate 220 lineal foot x 140 lineal foot aggregate drill pad
- Built 6' x 6' x 5' cellar to set and cement 60' of 16" steel conductor casing
- Dug rat hole and mouse hole for larger drill rig usage

